



Felicitation of ULBs (for operationalising FSSM)

By: Amrit Abhijat
Principal Secretary,
Principal Secretary, Department of
Urban Development,
Government of Uttar Pradesh

WORKSHOP ON FAECAL SLUDGE
AND SEPTAGE MANAGEMENT
(FSSM) IN UTTAR PRADESH
**Current Status and Future Pathways: The
Journey towards City-wide Inclusive
Sanitation**

Date: July 29, 2022



Sab ke liye swasth shahar

Swachhta ki nayi lehar



Selection Criteria for ULBs

Name of the ULB	Criteria for selection		
	Soft commissioning done	Bye laws prepared and approved by the ULB	Plant is functioning and treating sludge regularly
Chunar	Yes	Yes	Yes
Bijnor	Yes	Yes	Yes
Jhansi	Yes	Yes	Yes



Information-Bijnor

Facts about Bijnor FSSM

Type	Co- Treatment Plant
Capacity	20 KLD
Funding Agency	National Mission For Clean Ganga
Implementing Agency	Uttar Pradesh Projects Corporation Limited (UPPCL)
Technical Support	Centre for Science and Environment, Delhi
Built-up Area	225 Sqm
Commissioning	May 2022
Utilization of Plant	70%
Total FS Treated	300 KL till June 2022
Bye Laws Preparation	August 2019
Bye Laws Passed by council	February 2021
Gazettification	June 2022
Technology	Solid liquid separation at drying beds followed by liquid treatment at UASB reactor





Information-Chunar

Facts about Chunar FSSM

Type	Faecal Sludge Treatment Plant (FSTP)
Capacity	10 KLD
Funding Agency	National Mission For Clean Ganga
Implementing Agency	Uttar Pradesh Jal Nigam
Technical Support	Centre for Science and Environment, Delhi
Total Area	3250 Sqm
Builtup Area	1366 Sqm
Commissioning	March 2021
Utilization of Plant	100%
Total FS treated till date	2175 KL till June 2022
Bye Laws Preparation	August 2019
Bye Laws Passed by council	December 2021
Technology	Planted Drying bed with Anaerobic Baffle Reactor





Information-Jhansi

Facts about Jhansi FSSM

Capacity	6 KLD and 12 KLD
Funding Agency	ULB Funds (14 th FC)
Implementing Agency	Jhansi Municipality
Area	1000 Sqm for both 6 KLD and 12 KLD
Commissioning	6 KLD- March 2018 and 12 KLD- March 2021
Utilization of Plant	100%
Total FS Treated	5.08 Million Litre
Bye Laws Preparation	October 2021
Technology	Planted Drying bed with Anaerobic Baffle Reactor





Thank You